KADUR DISTRICT.

MARAMAT BRANCH.

Dated 26th January 1918.

Notice is hereby given that sealed tenders will be received at the office of the Deputy Commissioner, Kadur District, up to 12th February 1918, for restoring the undermentioned tanks in the taluks noted against them. An approximate estimate of quantities are not guaranteed. The work should be completed by the end of June 1918.

2. The plans, detailed estimates and conditions may be seen at the Deputy Commissioner's Office at Chikmagalur between 11 A.M. and 5 P.M.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board, in the Deputy Commissioner's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Mugali Tank, Register No. 636, Tarikere Taluk.

Items	Per	Rate	Quantity	Cost
Bund.		Rs. a., p.		
Earthwork including watering and tamping, etc., complete ...	C. yds.		6,700	
Puddle wall with good clay and gravel, ...	"		73	
Turfing to slopes	S. yd.		3,916	
New stone revetment	C. yd.		173	
Grade stones	Each		60	
Index stones	"		60	
B. M. stones	"		2	
Register No. stone	"		1	
Weir at left 110 feet long.				
Earthwork	C. yd.		25	
Surki concrete	C. ft.		193	
Burnt brick in surki mortar	"		555	
4" burnt stone slabs for coping	S. ft.		166	
Surki plastering	Sqr.		6 00	
Dry stone work	C. yd.		118	
Draft clearing (hard soil)	"		82	
Weir at right 160 feet long.				
Earthwork	C. yd.		263	
Surki concrete	C. ft.		185	
Burnt brick in surki mortar	"		131	
Surki plastering	Sqr.		5'0	
4" burnt stone slabs	S. ft.		80	
Dry stone work	C. yd.		3	
Sluice.				
Repairing the present sluice	L. S.		...	

Somanahalli Oorumundinakere, Register No. 456, Bidare hobli, Kadur Taluk.

Items	Per	Rate	Quantity	Cost
Bund.		Rs. a. p.		
Earthwork including watering and tamping, etc., complete ...	C. yd.		3,047	
Excavation for puddle wall and using the same for bund ...	"		32	
Puddle wall in breach	"		98	
Turfing the slopes	S. yd.		5,136	
Rough stone work, dry, new for revetment ...	C. yd.		228	
Do old do	"		100	
Providing grade stones with bed slabs	Each		40	
Do index stones do	"		40	
Do B. M. stones	"		2	
Do register and date stone	"		1	
Right weir.				
Earthwork excavation	C. yd.		176	
Filling foundation with surki concrete	C. ft.		579	
Burnt brick in surki mortar	"		782	
Burnt stone slabs	S. ft.		574	
Rough stone work, dry	C. yd.		115	
Plastering with surki mortar	Sq.		8'90	
Draft clearing	C. yd.		442	

M. G. SINGRACHARI,
For *Deputy Commissioner.*